



**Mercer Street Friends Food Bank
In conjunction and for
Arm-In-Arm**

**Request for Quotation for 11' x 11' x 8'7"
Leer walk-in freezer or approved equal.**

**Location: installation will take place at;
Arm In Arm, 1 N. Johnston Ave
Hamilton, NJ 08609**

Advertised Sealed Quote/Bid

Contact Person: **Sun Hae Kim**

Position: **Arm In Arm Director of
Administration**

Desired Delivery/Installation date is to be completed prior to: **June 1, 2023***

Ship to: Arm In Arm
1 N. Johnston Ave.
Hamilton, NJ 08609

Billed to: Mercer Street Friends Food Bank
824 Silvia Street
Ewing, NJ 08628

***Consideration will be given because of Manufacturers production date**

Please attached page(s) with detailed and descriptive specifications on provided sheets or attach your information in your company's format.

Item: 11' x 11' x 8'7" Leer walk-in freezer or approved equal with aluminum diamond plate floor, including labor and installation

(specifications listed on attached pages)

REQUIREMENTS:

- Site visit to 1 North Johnston Avenue Hamilton, NJ and arrangements can be made by contacting Sun Hae Kim and the contact number is **609-396-9355**.

This mandatory site visit must be completed before submitting quote/bid.

- The successful contractor **must use** the contractors as sub-contractor in the following categories if so requested/required by Arm-In-Arm.
- **Electrical, Plumbing, and Sprinkler system**

The names of these contractors will be given to the successful bidder.

Due Date of Bid is: Bid must be sealed to be accepted and delivered by 1pm Wednesday, March 29, 2023

Bid will be officially open on; Friday, March 31, 2023 at 11:00am

All sealed quote/bid are to be either dropped off and/or mailed to:

**Mercer Street Friends Food Bank
c/o James G. Allen
824 Silvia Street
Ewing, NJ 08628**

**Mercer Street Friends – Food Bank/Arm In Arm
Request for Quotation**

Product Name:

*Leer walk in freezer or approved equal,
11' x 11' x 8'7" high with aluminum diamond plate floor*

Description/Options:

- 5" thick urethane foam, stucco embossed cam-lock galvanize panels with 10-year warranty. 1 year hardware warranty
- 48" door with diamond plate exterior protection, heavy duty jamb guards and strip curtain
- Heated door frame and threshold
- 48" side x 42" long aluminum-covered outside ramp
- 48" LED light fixture with a switch at door, thermometer, and heated pressure relief vent
- Labor and material to receive and erect the new walk-in freezer.
- Russell 3 hp outdoor winterized condensing unit with 5-year Copeland compressor or approved equal warranty and new Russell or approved equal 3 fan blower coil with high-efficiency fan motors.
- Refrigeration labor and material to install the new 3 hp outdoor condensing unit, including a prefab pad, and hang a new matching blower coil inside the freezer.
- Labor for refrigeration/condensate piping must exit the building through a penetration cored-in building wall, which will be sealed upon completion.
- Code-approved sprinkler system.
- 60-day craftsmanship warranty
- Please attach all cut sheets denoting equipment/product.

Quote Sheet

(Please attach the following information)

All Quotes/Bid should be listed and/or attached in the following manner:

Base Pricing Leer Freezer or approved equal:	\$	
Labor, material, installation:	\$	
Condensing unit:	\$	
Labor, material installation:	\$	
Electrical work/needs:	\$	
Sprinkler system:	\$	
Permits:	\$	
Fees:	\$	
Concrete if required	\$	
List any Customer Discounts	\$	
Grand Total/submission bid price	\$	

Signed and dated by the company representative/installation manager, complete with contact information.

_____ **Signature & Title**

_____ **Date**

Contact Information: _____

Additional comments/information sheet(s): (please use/list if needed)

